


# Enhanced Energy Efficiency in Indian Data Centers ...



By M. L. Sinhal

## **From CMD's Desk ...**

*Growth shall be achieved keeping in mind that design must be most energy efficient and sustainable. National & Natural resources shall be used judiciously.*



1. What is Data Center ?
  - Configuration Components
  - Design Code
  - Main Power Components
2. Data Center Power Efficiency (PUE)
3. Server Air-Cooling Practices
4. Steps taken to reduce HVAC Power
5. Efforts to improve PUE & Reliability
6. The role of server designers for server heat removal
7. Green certification of RIL Data Centres





Data center



The storage space for a large group of networked computer servers typically used by organizations for processing, or distribution of large amounts of data is called Data Center.

- Data Center Building
  - Data Center Hall
  - Meet Me Rooms
  - Configuration areas
  - Battery Rooms
  - UPS Rooms
  - BMS Rooms
  - Security Control room
- Allied Utilities area
  - Efficient Electrical Power System
  - DG House
  - Chiller Plant & cooling tower
  - STP/ETP Plant
  - Administration Building

## A Telecommunications Infrastructure Standard for Data Centers - TIA-942


### Discipline Standards

1. IEC (Electrical)
2. ASHRAE (HVAC)
3. NBC (Building)
4. NFPA (Fire)


- Server Rack – IT Power
- HVAC
  - Chillers
  - Pumps
  - Cooling tower
  - Precision air conditioners
- Ancillary
  - Transformer
  - UPS
  - Lighting



- PUE is most common term used for Data center efficiency
- PUE is the ratio of,  
$$= \frac{\text{Total Facility power(KWh)}}{\text{IT Equipment Power(KWh)}}$$
- Lower the PUE, Better the Efficiency of Data center .
- PUE is also a function of geographical location of data centre




# Typical PUE Break Up



For this system  
PUE value is 1.5


Generally PUE  
varies from  
1.15 to 1.7

# Server Air-Cooling Practices




**Most Efficient Design**

# Most Efficient Heat Removal System




The **cold aisle** provides cold air directly to the front of all the racks and hence to the servers, while the **hot aisle** receives the warm air discharged by the servers after completing its cooling purpose.

# Switch and Server Air-Cooling Practice



Good Practice



Wrong Practice

# Steps taken to reduce HVAC Power


- Major step in reducing the PUE is reducing the Chiller power consumption.
- ASHRAE allowed the server inlet air temperature as **27 °C**.
- With this chiller operating temperatures are changed from **7 °C /12 °C to 20 °C /27 °C**.
- This has reduced the chiller power consumption from **0.66 ikw/TR to 0.32 ikw/TR**.
- PUE Reduced from **1.45 to 1.35**



- A typical Data Center Hall has servers of different make
- Different manufacturers follow different heat removal system
- If multiple servers of different makes are kept in the same hall, cooling arrangement suffers.
- To improve PUE and reliability, we undertook measures like:
  - diverting cold air and hot air
  - providing back plate
  - providing bottom plate
  - correcting main switch location

# Server Models & Air Directions



SERVER	AIR DIRECTION
SAMSUNG	Having air flow from bottom and discharge back
CEINA 6500	Front suction and front discharge
HP DL380	Cable manager obstruction exhaust air
TEJAS TJ1400/TJ-1600	Air from left /discharge right
NSN NOKIA	Server fan low static pressure
TOR SWITCHES	Some switch have back suction/front discharge
AL-NOKIA1830-PSS32	Front suction side discharge
AUDIO CODE	Jumper left air intake/ right air discharge
IBM	No filter in intake air
CIENA 5430	Front suction /back discharge 
HP 7000	
NSN NOKIA	



I feel all the Server manufacturers should come together for standardization of server air flow.

Server air flow shall be front entry and back discharge.

CII-IGBC & Lawrence Berkeley National Laboratory, USA should help the association of server manufacturers to make Data Center industry more energy efficient.



- PUE operating range of Reliance Data Centres is between **1.3 and 1.4**.
- RIL has applied for Green certification of its Data Centers.
- We are in advanced stages and expect to receive it soon.



# Thank You

By M. L. SINHAL