Data Center Modeling Demonstration You CAN Manage What You MODEL Lawrence Livermore National Laboratory (LLNL) Silicon Valley Leadership Group 5<sup>th</sup> Annual Data Center Efficiency Summit



Anna Maria Bailey Andy Ashbaugh



October 24, 2012

This work was performed under the auspices of the U.S. Department of Energy by Lawrence Livermore National Laboratory under Contract DE-AC52-07NA27344.

# Introduction

- Purpose
  - LLNL Data Center Master Plan
  - Key Competency Benchmarking/Modeling
- Goals Improve Overall Operations of B112 Enterprise Data Center
  - Evaluate optimization scenarios
  - Investigate efficiency improvements
    - Improve operational set point
    - Make building improvements
    - Identify consolidation
  - Present Results at SVLG
  - Develop whitepaper
- Team: LLNL, LBNL, Syska Hennessy, Romonet, California Energy Commission, DOE
- Timeline: August-October 2012
- Tool: Romonet Modeling Software

#### Master Plan Charter:

Develop projects to improve optimization of LLNL's data centers and reduce energy intensity



#### **Data Center Site**

#### **Computer Room**









Chiller Room

### **Data Center Modeling Demonstration**

- Introduction
- Model Construction
- Evaluate Model Accuracy
- Use Model to Forecast Efficiency
- Observations
- Plans

### **LLNL Data Center Overview**

- Building Information
  - Original Construction 1965, Retrofitted in 2007
  - 15,500 Sqft of Raised Floor
  - 14,000 Sqft of Infrastructure Space
- Electrical System
  - 2N UPS Systems (1,000 kVA Modules)
  - 2N & N Critical Power Distribution
  - 20 PDUs on the Raised Floor

IT Loads	2N (kW)	N (kW)
Capacity	630	480
Current Load	325	<b>7</b> (*Aug 2012)

- Mechanical Systems
  - Chilled Water System
  - N+1 Design
  - CRAH and AHU feeding under floor Constant Speed Fans

\* value during site visit, IT equipment load currently higher and expanding

#### **Project Process - What We Did**

- Survey site
- Create baseline model
- Compare baseline model results to

meter readings (actual IT power was the model input)

- Calibrate model (adjust component performance toward actual)
- Model with actual IT loads to investigate accuracy
- Model "What If" scenarios

#### **Example: Model Construction**



## Model Construction – Critical Electrical Dist.



### **Model Construction - Mechanical**



#### Comparison: Metering vs. Calibrated Romonet Results Critical Power



#### **Comparison: Metering vs. Calibrated Romonet Results Infrastructure Power**



### **Investigate "What If" Using Romonet**

- Increasing IT Load
  - Simulate IT load increase (332 kW to 1,110 kW)
- Adding CRAH / AHU Fan Speed Controls
- Adding Waterside Economizer
  - Dedicated Data Center Secondary Loop with elevated CHW Temperatures
  - Dedicated Data Center Cooling Tower

#### Waterside Economizer Flow Diagram



#### "What If" Analysis Comparison

#### **Annual Average PUE**



Not Included:

- Boiler Room (humidification) Gas Energy (missing data, unable to reconcile)
- Gen. Set Testing (gen. sets not installed at this site)

#### "What If" Analysis Comparison

#### **Annual Energy Contribution (MWh)**



#### "What If" Analysis Comparison

	Infrastructure Project Capital Expenditure	Annual Energy Cost	Simple Pay Back
Baseline	\$ O	\$ 400,000	
Projected IT Load	\$ O	\$ 1,020,000	DILANEN
CRAH & AHU VFDs	\$ 161,000	\$ 990,000	3 years
Waterside Economizer and VFDs	\$ 1,700,000	\$ 864,000	8 years

Energy cost \$0.065/kWh

# **Project Effort to Date**

(person days)		LLNL	Syska
Model Development	Data Collection: Paper Survey	1	
	Site Visit #1	1	1
	Develop Base Model		3
Model Calibration	Site Visit #2	1	1
	Analysis & Model Adjustment		3
Sub-Total		3	8
Model Change and Run "What If"	CRAH & AHU Fan Speed Control	.5	1
	Waterside Economizer	.5	3
Sub-Total		1	4
Sub-Total		4	12
Total			16

#### Modeler Experience: Subject Expert, Modeling Training Complete

#### What Did We Learn?

- Labor Required
  - Syska, LLNL, LBNL, Romonet
- Metering Issues
  - Slight variance in total metering
  - Variances encountered in UPS metering
    - Need to address with vendor during next maintenance cycle
- Office Tower Load (temporary Btu metering)
- Site Cooling Tower Water (not included in PUE)
- Chiller Performance Information
  - Not separately metered
  - Temporary load logging installed
  - Coordination required with rotation sequence of chillers

#### **Conclusions / What Next?**

- Accuracy- Testing was limited (one set of conditions): model accuracy deemed sufficient for "What If" investigation.
- The project uncovered a number of unknown metering issues.
- Adding IT load will provide the best ROI, in comparison other projects investigated will provide a much longer payback period.
- Work with customers to expand humidity level requirements. (Turn off or reduce boiler function)

### **Questions – LLNL Data Center Master Plan Team**

Andy Ashbaugh Lawrence Livermore National Laboratory 7000 East Ave PO Box 808 L-709 Livermore, CA 94550 Phone - (925)422-1137 Email - ashbaugh3@llnl.gov

Anna Maria Bailey, PE Lawrence Livermore National Laboratory 7000 East Ave PO Box 808 L-554 Livermore, CA 94550 Phone - (925)423-1288 Email – bailey31@IInl.gov

Marriann Silveira, PE Lawrence Livermore National Laboratory 7000 East Ave PO Box 808 L-554 Livermore, CA 94550 Phone - (925)423-5049 Email – silveira1@llnl.gov

Lawrence Livermore National Laboratory